

6-8-88 15-185-22021-0000

1 040119

API NUMBER 15- Completion Date 9/10/85

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE SW NW, SEC. 2, T. 23 S, R. 13 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 4101

3630 feet from S section line

4290 feet from E section line

Operator: Blackhawk Energy Corporation

Lease Name Mawhirter Well # 1

Name & Address P.O. Box 1910

County Stafford 124.35

Well Total Depth 3826 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 352

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor: Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 6:45 p.m. Day: 8 Month: 6 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 3824.5' Perfs 3432-34, 3532-35, 3565-68, 3598-3600, 3631-36'

1st plug sand back to 3380' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
6-21-88

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_

Operations Completed: Hour: 7:30 p.m. Day: 8 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3380' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED  
DATE 6-29-88  
INV. NO. 21100

Signed Stephen J. Pfeiffer (TECHNICIAN)