

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-20383-00-00
Spot: SWNESE **Sec/Twnshp/Rge:** 30-26S-8E
1712 feet from S Section Line, 1214 feet from E Section Line
Lease Name: SACO-DRUMM **Well #:** 2
County: BUTLER **Total Vertical Depth:** 2835 feet

Operator License No.: 35164
Op Name: JIM SNYDER, INC.
Address: PO BOX 109
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2830		80 SX
SURF	8.625	200		100 SX

Well Type: OIL **UIC Docket No:** _____ **Date/Time to Plug:** 12/21/2016 8:00 AM
Plug Co. License No.: 35164 **Plug Co. Name:** JIM SNYDER, INC.
Proposal Rcvd. from: LINDA SNYDER **Company:** JIM SNYDER **Phone:** (620) 344-6042

Proposed Plugging Method: AS PER KCC RUELS & REGS / SAND @ 2665' W/5 SXS, PERF & CIRC. 250'-0'.

Plugging Proposal Received By: JEFF KLOCK **WitnessType:** COMPLETE (100%)
Date/Time Plugging Completed: 12/30/2016 5:00 PM **KCC Agent:** DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH ON WIRELINE SET CIBP @ 2665', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. RIH ON WIRELINE PERFORATED SQUEEZE HOLES 250'-251'. 12-22-2016, RIH W/1" TUBING ON BACKSIDE OF 5.5" CASING @ 260', ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 95 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #3116. 12-28-2016, TAGGED CEMENT ON INSIDE 5-1/2" CASING @ 180', TAGGED CEMENT ON BACKSIDE 5-1/2" CASING @ 30'. 12-30-2016, ELITE CEMENTING MIXED & PUMPED 40 SXS 60/40 POZMIX 4% GEL TO SURFACE. P&A COMPLETE. 12-30-2016.

Top	Bot	Thru	Comments
2715	2730		CSG

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed _____

DUANE KRUEGER

(TECHNICIAN)

INVOICED Form CP-2/3
APR 19 2017

✓

1/2