

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-21965-00-00
Spot: NESWSE **Sec/Twnshp/Rge:** 30-26S-8E
1045 feet from S Section Line, 1693 feet from E Section Line
Lease Name: DRUMM **Well #:** 25
County: BUTLER **Total Vertical Depth:** 2781 feet

Operator License No.: 35164
Op Name: JIM SNYDER, INC.
Address: PO BOX 109
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2780		100 SX
SURF	8.625	222		125 SX

Well Type: OIL **UIC Docket No:** _____ **Date/Time to Plug:** 12/21/2016 8:00 AM
Plug Co. License No.: 35164 **Plug Co. Name:** JIM SNYDER, INC.
Proposal Rcvd. from: LINDA SNYDER **Company:** JIM SNYDER **Phone:** (620) 344-6042

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND @ 2650' W/5 SXS, PERF & CIRC. 270'-0'.

Plugging Proposal Received By: JEFF KLOCK **Witness Type:** COMPLETE (100%)
Date/Time Plugging Completed: 12/28/2016 5:00 PM **KCC Agent:** DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH ON WIRELINE SET CIBP @ 2650', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. RIH ON WIRELINE PERFORATED SQUEEZE HOLES 270'-271'. 12-22-2016, SWEDGED INTO 5-1/2" CASING, ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL, WELL LOST CIRCULATION. SDON. 12-23-2016, RIH W/1" TUBING ON BACKSIDE OF 5.5" CASING @ 260', ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN 1" TUBING. RIH W/1" TUBING ON INSIDE 5.5" CASING @ 260', ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. TOPPED WELL BACK TO SURFACE W/25 SXS, TOTAL 125 SXS. CEMENT TICKET #3118. 12-28-2016, TAGGED CEMENT @ SURFACE. P&A COMPLETE 12-28-2016.

Top	Bot	Thru	Comments
2700	2716		CSG

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

INVOICED
APR 19 2017

Form CP-2/3