

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22546-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 30-26S-8E
957 feet from S Section Line, 2356 feet from E Section Line
Lease Name: DRUMM Well #: 28
County: BUTLER Total Vertical Depth: 2802 feet

Operator License No.: 35164
Op Name: JIM SNYDER, INC.
Address: PO BOX 109
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2755		
PROD	5.5	2797		100 SX
SURF	8.625	206		120 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/21/2016 8:00 AM
Plug Co. License No.: 35164 Plug Co. Name: JIM SNYDER, INC.
Proposal Rcvd. from: LINDA SNYDER Company: JIM SNYDER, INC. Phone: (620) 344-6042

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND @ 2665' W/5 SXS, PERF & CIRC. 260'-0'.

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/30/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH ON WIRELINE SET CIBP @ 2665', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. RIH ON WIRELINE PERFORATED SQUEEZE HOLES 260'-261'. 12-22-2016, RIH W/ 1" TBG @ 266', WELL WOULD NOT CIRCULATE TO SURFACE. LAYED DOWN 1" TUBING. CUT SLIPS FROM CASING, & COMPLETED CELLAR WORK. RIH W/1" TUBING ON BACKSIDE OF 5.5" CASING @ 266', ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 70 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN 1" TUBING. RIH W/ 1" TUBING ON INSIDE 5.5" CASING @ 266', ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. TOTAL 105 SXS. CEMENT TICKET #3115. 12-28-2016, TAGGED CEMENT ON BACKSIDE @ SURFACE, INSIDE @ 210'. 12-30-2016, ELITE CEMENTING MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL TO SURFACE. P&A COMPLETE. 12-30-2016.

Top	Bot	Thru	Comments
2718	2739	CSG	

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN) INVOICED

APR 19 2017 Form CP-2/3

JK

1/1