

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-19085-00-01
Spot: SESWSW Sec/Twnshp/Rge: 35-20S-13W
330 feet from S Section Line, 4290 feet from E Section Line
Lease Name: SHARP A Well #: 1
County: BARTON Total Vertical Depth: 3545 feet

Operator License No.: 33288
Op Name: MANNING, GREGORY
Address: 574 SE 130 AVE
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3527		125 SX
SURF	8.625	182		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/24/2017 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: GREG MANNING Company: MANNING, GREGORY DBA Phone: (620) 564-2302

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 15 sx gel.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/24/2017 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1300', 735' and 175'. Ran tubing to 3500' and pumped 75 sx cement w/300 # hulls. Pulled tubing to 2800' and pumped 15 sx gel. Pulled tubing to 1300' and pumped 60 sx cement w/200 # hulls. Pulled tubing to 750'. Circulated cement to surface on casing with 210 sx cement. Shut in casing and circulated cement to surface on surface pipe with 55 sx cement. Pulled tubing and topped off with 20 sx cement.

GPS: 38.26172 -098.73411

Perfs:

Top	Bot	Thru	Comments
3527	3532		
3276	3471		

KCC WICHITA
APR 19 2017
RECEIVED

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG 706

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

INVOICED

APR 19 2017

Form CP-2/3

APR 13 2017