

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-23016-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 33-16S-13W
2310 feet from S Section Line, 330 feet from W Section Line
Lease Name: BRADSHAW Well #: 4
County: BARTON Total Vertical Depth: 3450 feet

Operator License No.: 31528
Op Name: MIKE KELSO OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3450		150 SX
SURF	8.625	408		235 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/11/2017 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO OIL, INC. DBA Phone: (620) 562-8088

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 300 # hulls and 10 sx gel. Well has 4 1/2" liner from top to bottom.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2017 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 870' and 400'. Ran tubing to 3340' and pumped 10 sx gel followed by 40 sx cement. Pulled tubing to 1400' and pumped 40 sx cement w/100 # hulls. Pulled tubing to 900' and pumped 40 sx cement. Pulled tubing to 400'. Circulated cement to surface on casing with 50 sx cement. Pulled tubing. Tied to casing and circulated cement to surface on backside with 60 sx cement. Will cut off braden head and top off.

GPS: 38.61514 -098.77457

Perfs:

Top	Bot	Thru	Comments
3385	3388		

KCC WICHITA
APR 19 2017
RECEIVED

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed

Bruce Rodie
(TECHNICIAN)

APR 19 2017

CM

APR 17 2017