

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-23960-00-00
Spot: E2NESE Sec/Twnshp/Rge: 33-16S-13W
1980 feet from S Section Line, 330 feet from E Section Line
Lease Name: BRADSHAW Well #: 8
County: BARTON Total Vertical Depth: 3482 feet

Operator License No.: 31528
Op Name: MIKE KELSO OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	0		Unknown depth
PROD	5.5	3478		150 SX
SURF	8.625	871		400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/28/2017 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO OIL, INC. DBA Phone: (620) 562-8088

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 300 # hulls and 10 sx gel. Well has 4 1/2' liner that is not on records.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/28/2017 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400' and 870'. Ran tubing to 3300' and pumped 10 sx gel followed by 40 sx cement w/100 # hulls. Pulled tubing to 1400' and pumped 40 sx cement w/100 # hulls. Pulled tubing to 850' and pumped 30 sx cement. Pulled tubing to 400'. Circulated cement to surface on casing with 45 sx cement. Pulled tubing, tied to casing and pumped 10 sx cement pressured to 1000 psi.

GPS: 38.61436 -098.75832

Perfs:

Top	Bot	Thru	Comments
3380	3384		

KCC WICHITA
APR 19 2017
RECEIVED

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG TPG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

INVOICED
APR 19 2017
CM

APR 13 2017