

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-207-20558-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 30-23S-17E  
2475 feet from S Section Line, 1340 feet from W Section Line  
Lease Name: BRODMERKLE Well #: 8  
County: WOODSON Total Vertical Depth: 953 feet

Operator License No.: 34008  
Op Name: OWENS PETROLEUM LLC  
Address: 1274 202ND RD  
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	950		95 SX
SURF	7	40		20 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/19/2017 12:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: SCOTT OWENS Company: \_\_\_\_\_ Phone: (620) 496-7048

Proposed Plugging Method: Fill to surface with cement

Plugging Proposal Received By: RYAN DULING WitnessType: NONE  
Date/Time Plugging Completed: 01/19/2017 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe down the inside of the 2" casing that was cemented inside the 7" surface casing to TD. Pumped and circulated cement through the 1" pipe inside the 2" casing from TD to surface. Pulled the 1" pipe out of the casing. Hooked onto the 2" casing and pumped cement down the 2" casing from surface. Pressured well up to 500 psi and shut in. A total of 35 sacks of portland cement was reported used to plug this well.

RECEIVED  
KCC DIST # 3  
APR 13 2017  
CHANUTE, KS

RD

Remarks:

Plugged through: TBG

District: 03

Signed

E.C.R.S.  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

APR 17 2017  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
APR 19 2017

Form CP-2/3