

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-04753-00-00  
Spot: NWNESWSW Sec/Twnshp/Rge: 3-20S-9W  
1306 feet from S Section Line, 4331 feet from E Section Line  
Lease Name: MITCHELL Well #: 2  
County: RICE Total Vertical Depth: 3224 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3216		100 SX
SURF	8.625	208		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/13/2017 11:30 AM  
Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.  
Proposal Rcvd. from: RANDY GINEST Company: RAMA OPERATING CO Phone: (620) 546-3388

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/13/2017 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS AND TUBING. TRIED SETTING CIBP,, CASING TOO ROUGH, SO RUN TUBING TO 3100' AND PUMP 50 SX'S COMMON WITH 3% CC. PULL TUBING TO 1100, RUN SLIM GUN DOWN TO 1150' AND PERFORATE. RUN TUBING BACK TO 1150' AND PUMP 35 SX'S COMMON CEMENT WITH 3% CC. WAIT AWHILE, ATTEMPTED TO TAG, COULD NOT. PUMPED 35 SX'S AT 1150', WAIT AWHILE, ATTEMPTED TO TAG- COULD NOT. PUMPED 35 MORE SX'S AT 1150', WAITED AWHILE AND TAGGED AT 1000'. PULL TUBING TO 700' AND RUN SLIM GUN DOWN TO 750' AND PERFORATE. RUN TUBING BACK DOWN TO 750' AND PUMP 35 SX'S COMMON CEMENT WITH 3% CC. PULL TUBING OUT OF HOLE. PERFORATE AT 260', RUN TUBING BACK DOWN TO 260' AND CIRCULATE CEMENT TO SURFACE FROM BOTH CASINGS. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3216	3224	OH	

Remarks: GEMINI PERF TICKET #2919. BASIC SERVICES CEMENT TICKET #14924. TA N.O.V.

Plugged through: TBG

District: 02

Signed [Signature] DISTRICT SUPERVISOR  
(TECHNICIAN)

Form CP-2/3

INVOICED  
APR 19 2017