

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-113-21276-01-00
Spot: SESWSENW Sec/Twnshp/Rge: 19-20S-5W
2777 feet from S Section Line, 3417 feet from E Section Line
Lease Name: BARNHART Well #: 22-19H
County: MCPHERSON Total Vertical Depth: 5125 feet

Operator License No.: <u>3911</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>RAMA OPERATING CO., INC.</u>	CIBP	7	3526		
Address: <u>101 S MAIN ST</u>	PROD	7	3561		275 SX
<u>STAFFORD, KS 67578</u>	SURF	10.75	221		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2017 10:00 AM
Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.
Proposal Rcvd. from: RANDY GINEST Company: RAMA OPERATING CO Phone: (620) 546-3388

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 04/12/2017 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, PULL RODS AND TUBING. SET CIBP AT 3526' AND CAP WITH 10 SX'S CEMENT. PERFORATE AT 800', 430' AND 275'. RUN TUBING TO 800' AND PUMP 50 SX'S COMMON CEMENT WITH 3% CC. PULL TUBING TO 430'. WAIT 1 HR AND TAG CEMENT AT 750'. PUMP 50 SX'S COMMON CEMENT WITH 3% CC AT 430', PULL TUBING TO 275' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Top	Bot	Thru	Comments
3361	4850		

Remarks: GEMINI PERF TICKET #2917. BASIC SERVICES CEMENT TICKET #15020.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

Form CP-2/3

INVOICED

APR 19 2017