

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-25977-00-00
Spot: NWNENWSW Sec/Twnshp/Rge: 12-15S-17W
2480 feet from S Section Line, 960 feet from W Section Line
Lease Name: WELLBROCK Well #: 1-12
County: ELLIS Total Vertical Depth: 3597 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13.375	93		100 SX
PROD	5.5	3595		150 SX
SURF	8.625	1060		425 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/31/2017 10:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE Phone: (620) 655-4494

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 3192' - 3194', 3217' - 3221', 3272' - 3276', 3328' - 3331', 3348' - 3351', 3380' - 3386', 3485' - 3488' and 3490' - 3492'.
PBTB - 3578'.
CIBP - 3484'

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/31/2017 3:40 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Alliance set CIBP at 3100'. Spotted 2 sx cement on top of CIBP. Cut 5 1/2" casing at 1708' and pulled casing. Ran in hole with tubing to 1642; and pumped 165 sx cement w/300 # hulls mixed in. Pulled tubing to 1042' and pumped 100 sx cement w/100 # hulls mixed in. Pulled tubing to 473' and pumped 135 sx cement w/100 # hulls mixed in to circulate cement to surface. Pooled over hole. Pulled tubing. Hole standing full.

GPS: 38.76193 -099.16786

Perfs:

Top	Bot	Thru	Comments
3380	3386		
3348	3351		
3328	3331		
3217	3221		
3192	3194		


KCC WICHITA
APR 19 2017
RECEIVED

Remarks: QUALITY CEMENTING CO TICKET # 137

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

APR 03 2017

INVOICED
APR 19 2017

Form CP-2/3