

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-033-21639-01-00
 Spot: SESWSESE Sec/Twnshp/Rge: 24-34S-18W
213 feet from S Section Line, 982 feet from E Section Line
 Lease Name: BROCK 3418 Well #: 1-24H
 County: COMANCHE Total Vertical Depth: 5386 feet

Operator License No.: 34192
 Op Name: SANDRIDGE EXPLORATION AND PRO
 Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5350		WITH 100 SX CMT
COND	20	120		WITH 10 SX CMT
	11 9.625	965	1505	WITH 540 SX CMT
	L1 4.5	9747	0	5408-9747 WITH 470 SX CMT
PROD	7	5840	3000	WITH 240 SX CMT
SURF	13.375	435		WITH 840 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/28/2017 2:00 PM
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
 Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 5350' WITH 100 SX CMT. PLUG AT 990' WITH 75 SX CMT. PLUG AT 480' WITH 100 SX CMT. PLUG AT 60' WITH 40 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: PARTIAL
 Date/Time Plugging Completed: 03/28/2017 4:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5350'. CIRCULATED HOLE WITH 190 BBL MUD THEN SPOTTED 100 SX CMT ON TOP OF CIBP. 1ST PLUG AT 990' WITH 75 SX CMT. 2ND PLUG AT 480' WITH 100 SX CMT. 3RD PLUG AT 60' WITH 40 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
8550	8869		
8400	8498		
7793	8103		
7424	7729		
7044	7364		
6284	6577		
5888	6130		
5544	5830		


Remarks: USED 60/40 POZMIX 4% GEL 2% CC BY ORR ENTERPRISES. TMD = 9747'

Plugged through: TBG

District: 01

RECEIVED
 APR - 4 2017
 KCC DODGE CITY

Signed


 (TECHNICIAN)

INVOICED
 APR 19 2017