

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-26865-00-00  
Spot: NWNESESE Sec/Twnshp/Rge: 28-14S-16W  
1050 feet from S Section Line, 370 feet from E Section Line  
Lease Name: VONLINTEL Well #: 1  
County: ELLIS Total Vertical Depth: 3425 feet

Operator License No.: 4787  
Op Name: TDL, INC.  
Address: 1310 BISON RD  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	224		150 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/20/2017 12:00 AM  
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.  
Proposal Rcvd. from: LARRY Company: SOUTHWIND DRILLING, INC. Phone: (620) 617-3478

Proposed Plugging Method: Ordered 285sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/20/2017 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st plug @3400 w/50 sx  
2nd plug @1000 w/50 sx  
3rd plug @400 w/80 sx  
4th plug @275 w/50 sx  
5th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Perfs:

KCC WICHITA  
APR 19 2017  
RECEIVED

Remarks: GLOBAL

Plugged through: DP

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED  
APR 19 2017

CM

MAR 21 2017

Form CP-2/3