

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19237-00-00
Spot: NWSENWSW Sec/Twnshp/Rge: 20-33S-3E
1689 feet from S Section Line, 4359 feet from E Section Line
Lease Name: WEST RAINBOW BEND UNIT Well #: 14
County: COWLEY Total Vertical Depth: 3262 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3241		100 SX
SURF	8.625	259		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/13/2017 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: MIKE ANSTINE Company: _____ Phone: (620) 218-1822

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/13/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH W/TUBING @ 3258', ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 25 SXS CLASS A 2% GEL 2 1/2% CC & DISPLACED IN CASING. TAGGED CEMENT @ 3130'. RIH W/TUBING @ 367', ELITE ESTABLISHED CIRCULATION, MIXED & PUMPED 45 SXS CLASS A 2% GEL 2 1/2% CC TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #3232.


Top	Bot	Thru	Comments
3241	3262	OH	

Remarks: BACKSIDE HAS CEMENT @ SURFACE.

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

Form CP-2/3

INVOICED
APR 19 2017

✓