

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-033-21127-00-00  
Spot: NESESWSW Sec/Twnshp/Rge: 31-31S-19W  
637 feet from S Section Line, 4103 feet from E Section Line  
Lease Name: BUTLER A Well #: 1  
County: COMANCHE Total Vertical Depth: 6000 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5150		WITH 2 SX CMT
COND	20	94		
	11 8.625	709		WITH 325 SX CMT
PROD	4.5	5435	0	WITH 250 SX CMT
SURF	13.375	322		WITH 175 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/04/2017 9:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Revd. from: BRAD TATRO Company: WOOLSEY OPERATING Phone: (620) 886-5606

Proposed Plugging Method: CIBP @ 5150' WITH 2 SX CMT. PLUG AT 1230' WITH 50 SX CMT. 100# HULLS IN LAST 25 SX CMT. PLUG AT 740' TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/04/2017 10:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5150' WITH 2 SX CMT. PERFORATED AT 1230' & 740'. RAN TBG TO 1232' & PUMPED 25 SX CMT THEN 25 SX CMT WITH 100# HULLS. PULLED TBG. TIED ONTO 4 1/2" CASING & PUMPED 210 SX CMT CIRCULATING CMT THROUGH THE 740' PERFORATIONS AND UP THE 4 1/2" X 8 5/8" ANNULUS TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5230	5236		
5198	5203		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED  
APR - 6 2017  
KCC DODGE CITY

Signed

  
JA  
(TECHNICIAN)/INVOICED

APR 19 2017 Form CP-2/3