

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-20551-00-00
Spot: SENESEW Sec/Twnshp/Rge: 18-15S-12W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease Name: PARKER ESTATE Well #: 3
County: RUSSELL Total Vertical Depth: 2897 feet

Operator License No.: 30705
Op Name: YOUNGER ENERGY COMPANY
Address: BUILDING 400 9415 E. HARRY STREE
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3258		125 SX
SURF	8.625	245		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/05/2017 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DON BROWNING Company: YOUNGER ENERGY COMPANY DB Phone: (785) 810-8230

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/800 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/05/2017 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1250' and 790'. Hole in casing from 300' - 350'. Ran tubing to 2652' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 1405' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 517' and pumped 20 sx cement. Circulated cement to pit. POOH. Hooked to casing and pumped 10 sx cement at 350 psi. Hooked to braden head and pumped 20 sx cement at 250 psi. Cement in casing down 8' - 10'.

GPS: 38.74496 -098.69971

Perfs:

Top	Bot	Thru	Comments
3053	3202		
2882	2890		
2695	2700		

KCC WICHITA
APR 19 2017
RECEIVED

Remarks: GLOBAL OILFIELD SERVICE TICKET # 27652

Plugged through: TBG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

APR 19 2017

APR 06 2017

Form CP-2/3