

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-21630-00-00
Spot: SESESE Sec/Twnshp/Rge: 11-34S-10W
339 feet from S Section Line, 316 feet from E Section Line
Lease Name: SHELLHAMMER Well #: 1
County: BARBER Total Vertical Depth: 5025 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4525		WITH 2 SX CMT
CIBP	5.5	4620		
PROD	5.5	5015	3230	WITH 125 SX CMT
SURF	8.625	249		WITH 175 SX CMT

Well Type: OG - (GAS) UIC Docket No: _____ Date/Time to Plug: 03/15/2017 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 4525' & 2 SX CMT. PLUG AT 650' WITH 10 SX GEL & 50 SX CMT. PLUG AT 275' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/15/2017 4:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

SET CIBP @ 4525' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 650' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 260' WITH 50 SX CMT. 3RD PLUG AT 42' WITH 20 SX CMT.

Top	Bot	Thru	Comments
5015	5024	OH	
4582	4587	CSG	

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE. CONTROL # 2017-0026-001

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
MAR 21 2017
KCC DODGE CITY

Form CP-2/3

KMS