

1509-15132-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Barton County. Sec. 34 Twp. 16 Rge. 11 (E) 11 (W)

Location as "NE/CNW/SWK" or footage from lines SE SE SE

Lease Owner Hinkle Oil Company

Lease Name Kroutwurst Well No. 6

Office Address 914 Union National Bank Bldg., Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Abandoned

Date well completed 4-13-50 19

Application for plugging filed 2-23-53 19

Application for plugging approved 2-23-53 19

Plugging commenced Pulling started 2-23-53 19


Plugging completed 3-4-53 19

Reason for abandonment of well or producing formation not producing oil in

paying quantities

If a producing well is abandoned, date of last production December 1952 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3395' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	264'	none
				5 1/2"	3395'	2822'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud to 300 feet  
Set rock bridge at ~~200~~ 300' to 285'  
Run 25 sax cement  
mud to 40'  
Set 10' rock bridge and ran 10 sax cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company  
Address Chase, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
J. B. HINKLE (employer or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. B. Hinkle

SUBSCRIBED AND SWORN to before me this 9th day of April, 19 53

My commission expires Jan. 17, 1954.

Murphy A. Repton Notary Public.

**PLUGGING**  
FILE SEC 34 T 16 R 11 W  
BOOK PAGE 83 LINE 6

24-2675-S 2-52--20M

APR 1 1953 4-10-53  
CONSERVATION DIVISION  
Wichita, Kansas

15009-15132-0000

Casing  
8" 264' - 200' lat  
5" 3395' - 30' "

Kroutwurst No. 6. SE SE SE 34-16-11 Barton County, Kansas.  
Hinkle Oil Company  
Contractor. J. B. Hinkle.  
Commenced 4-2-50 Completed 4-13-50  
Elevation 1939

0	85	surface
85	235	grey shale and shells
235	260	lime and shale
260	300	red bed and sand
300	750	shale and shells
750	780	Anhydrite
780	857	lime and shale
857	1080	shale and shells
1080	1470	shale, shale and lime shells
1470	1850	lime and shale
1850	2120	lime
2120	2515	lime and shale
2515	2570	lime
2570	2971	lime and shale
2971	3045	sandy lime and shale breaks
3045	3240	lime and shale
3240	3395	lime

Tops:	
Topeka	2936
Heebner	2989
Br. Lime	3088
Lansing	3114
Conglomerate	3379
Arbuckle	3393 -

**PLUGGING**  
 FILE SEC 34 T 16 R 11 W  
 BOOK PAGE 23 LINE 6

APR 10 1950  
 CONSERVATION DIVISION  
 Wichita, Kansas