

15-009-15130-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County, Sec. 34 Twp. 16 Rge. 11 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____

SE SW SE
Lease Owner Hinkle Oil Company
Lease Name Krautwurst #4 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 10/18/76 _____ 19____
Plugging completed 10/25/76 _____ 19____
Reason for abandonment of well or producing formation _____
depleted.
If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3381
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	112	none
				5 1/2"	3381	455'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran sand to 3350' and ran 5 sacks cement. Pipe was parted, pulled 16 joints.
Pumped 2 sacks hulls, 110 sacks cement w/8% gel.

PLUGGING COMPLETE.

RECEIVED

STATE CORPORATION COMMISSION

OCT 29 1976

10-29-76

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS


STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS

SUBSCRIBED AND SWORN TO before me this 27th day of October, 19 76

Margaret Melcher
Notary Public.

My commission expires



15009-15130-0000

Casing record.
8 5/8" 112'
5 1/2" 3381'

Kroutwurst No. 4. SE SW SE 34-16-11 Barton Co. Kansas.
Hinkle Oil Company,
Contractor, J. B. Hinkle.
Well commenced 2-25-50 Completed 3-8-50
Elevation 1940

0	55	Red clay and shale
55	108	Cement
108	500	shale and shells
500	795	red bed and shale
795	1350	shale and shells
1350	1740	lime and shale
1740	2040	lime
2040	2720	lime and shale
2720	3035	lime
3035	3100	lime and shale
3100	3381	lime

Tops:

Oolitic zone of Topeka	2937-3946
Top Heebner Shale	2990 (-1050)
Base Oread	3021 (-1081)
Top Brown Lime	3096 (-1156)
Top Lansing	3114 (-1174)
Coarse oolitic limestone	no shows 3208-3224
Top Sooy Conglomerate	none
Top Arbuckle	3375 (-1435)
Coarsely rhombohedral white dolomite with interstitial porosity and saturation 3375-3381	
T. D.	3381

RECEIVED
STATE CORPORATION

OCT 26 1976

CONSULTANT
Wichita, Kansas

State of Kansas)
County of Sedgwick) ss

I hereby certify that the above is a true and correct log as compiled from the daily drilling reports kept on said well.

And further affiant saith not.

Orvie Howell
Orvie Howell

Subscribed to and sworn to before me this 20th day of October, 1976.

Marcia Spicer
Marcia Spicer

My commission expires July 27, 1977

