

15-009-15127-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.,
245 North Water
Wichita, KS 67202

Barton County, Sec. 34 Twp. 16 Rge. 11 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines _____

Lease Owner SW NW Hinkle Oil Company
Lease Name Frees #1 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12/6/78 19____
Plugging completed 12/6/78 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3377
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	104	none
				5 1/2"	3377	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 75 sacks cement, 1 sack hulls, 25 sacks gel, 1 sack hulls and 75 sacks 50/50 pos with 4% gel.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

DEC - 8 1978
12-8-78

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 19 78

My commission expires _____



Margaret Melchior
Notary Public.

15 009-15 127-0000

Casing record.
104" 8 5/8"
3377" 5"

Free No. 1. SW NW 34-16-11 Barton County, Ks.
Hinkle Oil Company, et al.
Contractor. J. B. Hinkle.
Commenced 9-7-50 Completed 9-17-50
Elevation 1937

0	40	top soil and rock
40	104	shale and sand
104	750	shale and shells
750	790	Anhydrite
790	1325	shale and shells
1325	2020	lime and shale
2020	2160	shale and shells
2160	2315	shale and lime
2315	2455	shale and sandy lime
2455	2945	lime and shale
2945	2995	lime
2995	3294	lime and shale
3294	3323	lime
3323	3375	lime and shale
3375	3377	Dolomite

Tops:	Eopoka	2730	(-841)
	Heebner	2986	(-1047)
	Br. Lime	3086	(-1149)
	Lansing	3103	(-1169)
	Artuckle	3375	(-1436)

RECEIVED
STATE COMMISSION
JUN 19 1978

State of Kansas)
County of Sedgwick) ss

I hereby certify that the above is a true and correct log as compiled from the daily drilling reports kept on said well.

And further affiant saith not.

J. B. Hinkle

Subscribed to and sworn to before me this 29th day of September, 1950.

Marshall C. Watson
N.P.

My commission expires 1-17-54