


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barton County. Sec. 34 Twp. 16 Rge. 11 E/W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines  
SW NE NE  
Lease Owner American Petrofina Co. of Texas  
Lease Name Frees A#7 Well No.  
Office Address Russell, Kansas 67665  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above Section Plat

Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 8/14/76 19  
Plugging completed 9/8/76 19  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rankin  
Producing formation Depth to top Bottom Total Depth of Well 3374  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	DEPTH	PULLED OUT
				8-5/8	320	none
				5 1/2"	3371	542'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3350' and ran 5 sacks cement thru dump bailer. Pipe parted, pulled 17 joints. Pumped 2 sacks hulls, 5 sacks gel and set plug, pumped 100 sacks cement.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 17 1976  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.

R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS  
(Address)

Subscribed and sworn to before me this 15th day of September 19 76

Margaret Melcher  
Notary Public.

My commission expires



15009-03209-0000

STERLING DRILLING COMPANY

STERLING, KANSAS

WELL LOG ----- Frees "A" #7

Location - C SW/4 NE/4 NE/4 of Section 34-16S-11W, Barton County, Kansas

Owner - The El Dorado Refining Company  
Contractor - Sterling Drilling Company

Commenced - 7-17-50  
Completed - 7-27-50 (w/r)

Total Depth - 3376' (w/r)

Total Depth - 3374' D.F.

RECEIVED  
STATE DEPARTMENT OF CONSERVATION

JUL 22 1950

Elevation: 1942 D. F.

LOG

CASING RECORD

0- 318	Clay, Shale and Shells
318- 750	Shale and Shells
750- 755	Anhydrite
755-1390	Shale, Shells and Salt
1390-1440	Shale and Shells
1440-1640	Shale and Lime
1640-2155	Lime
2155-2715	Shale and Lime
2715-2995	Lime
2995-3090	Shale and Lime
3090-3373	Lime
3373-3376	Arbuckle Lime

320 Feet of 8-5/8" Surface Pipe  
Cemented with 150 Sacks Cement

3375.74 Feet of 5 1/2" O. D. Casing  
Cemented with 80 Sacks Cement

CONSERVATION DIVISION  
Wichita, Kansas

PRODUCTION: ~~Producer~~  
Drawdown 2914 BOPD, N.M.

FORMATION TOPS:

Heebner	2987
Dodge	3003
Br. ls.	3088
Lansing	3104
Arbuckle	3370
No Congl.	

R.T.D. 3373, fair odor, good-fair por. good S.F.O.  
Drlg. shoe, fluid kicked tools up hole. Had 1400'  
GPH/20 mins. thru bridge.  
D.D. to 3374, T. D.  
2950' OIH/3 hrs. @ 166.68 BO/3 hrs 1600' O.B.

CC: Kansas Well Log Bureau  
508 E. Murdock  
Wichita

El Dorado Office

Russell Office ✓

# 7