


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Barton County. Sec. 34 Twp. 16 Rge. 11 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE SW NE
Lease Owner American Petrofina Co. of Texas
Lease Name Frees A#6 Well No.
Office Address Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole)

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 8/17/76 19
Plugging completed 9/8/76 19
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rankin
Producing formation Depth to top Bottom Total Depth of Well 3387
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	270	none
				5 $\frac{1}{2}$ "	3382	521

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3360' and ran 5 sacks cement thru dump
bailer. Shot pipe at 2525', pipe parted, pulled 17 joints. Pumped 2 sacks hulls,
4 sacks gel, set plug and pumped 100 sacks cement.

PLUGGING COMPLETE.

9-17-76

RECEIVED
CORPORATION COMMISSION

SEP 17 1976

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE ss.

R. DARRELL KELSO

(employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature)

CHASE, KANSAS

(Address)

Subscribed and Sworn to before me this 15th day of September 1976

My commission expires



Notary Public.

15009-03208-0000

WELL LOG ----- No. 6 FREES "A"

Location - C NE SW NE Sec. 34-16S-11W, Barton County, Kansas

Owner - The El Dorado Refining Company

Contractor - Sterling Drilling Company

Commenced - 12-19-49

Completed - 1-10-50

Total Depth - 3387

Elevation: 1951

LOG

Clay, shale & shells	270
Sand, shale	690
Red bed & shale	760
Anhydrite	790
Shale & shells	1520
Lime	1785
Lime & shale	1879
Lime	2110
Lime & shale	2415
Shale	2525
Shale & lime	2710
Lime	3020
Dolomitic lime	3040
Sandy shale	3104
Lime	3315
Lime & shale	3382
Dolomite	3387

Total Depth

CASING RECORD

270' 8-5/8" surface pipe

3379' 5 1/2" w/75 sx.

FORMATION TOPS D.F.

Heebner	3001
Dodge	3019
Lansing	3119
Arbuckle	3380

PRODUCTION

441 BOFD, No Water

RECEIVED
COMMISSION
JAN 28 1950
COMMISSIONER OF GEOL.
Wichita, Kansas