


15-009-15147-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County, Sec. 35 Twp. 16 Rge. 11 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner American Petrofina Company of Texas
Lease Name Frees "B" Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed January 20, 19 49
Application for plugging filed December 29 19 60
Application for plugging approved January 3 19 61
Plugging commenced 1-14-61 19
Plugging completed 1-18-61 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production August 22 19 60
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3387 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	255'	None
				5-1/2"	3380'	2851'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3380', ran 25 gal. of sand from 3380' to 3370' and dumped 5 sacks of cement with dump bailer. Pulled 5 1/2" casing. Checked fluid to 260', set 10' rock bridge to 250' and dumped 25 sacks of cement. Mudded to 40', set 10' rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

STATE CORPORATION COMMISSION

JAN 27 1961

CONS. DIVISION

WICHITA, KANSAS

1-27-61

Name of Plugging Contractor KNIGHT CASING PULLING CO.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas

SUBSCRIBED AND SWORN TO before me this 24th day of January, 19 61

My commission expires May 20, 1964 Milton J. Volin Notary Public.



Well Log: Frees "B" No. 1

Location: NW/c NW/4 SW/4 of Section 35-16S-11W, Barton County, Kansas

Owner: American Petrofina Company of Texas

Contractor: Sterling Drilling Company, Sterling Kansas

Commenced: 12/27/48

Completed: 1/8/49 (w/r)

Total Depth: 3387' (w/r)

	<u>LOG</u>	<u>CASING RECORD</u>
0 - 40	Surface	255' 8 5/8" surface pipe cemented
40 - 256	Clay, sand & shale	w/200 sacks cement.
256 - 755	Shale & shells	
755 - 785	Anhydrite	Ran 117 joints 5 1/2" casing
785 - 1250	Shale & shells	
1250 - 1430	Salt and shale	
1430 - 1450	Shale and shells	
1450 - 1815	Shale and lime	
1815 - 2030	Lime	
2030 - 2200	Shale and Lime	
2200 - 2360	Shale and shells	
2360 - 2515	Shale	
2515 - 2705	Shale and lime	
2705 - 3030	Lime	
3030 - 3090	Shale and broken lime	
3090 - 3345	Lime	
3345 - 3380	Shale	
3380 - 3387	Arbuckle lime	

PRODUCTION

Producer.

Rec'd fr: Sterling Drlg. Co. 1/29/49.

cc: Frank Brooks

Levi Sherman

Well Log Bureau

Corp. Comm.

RECEIVED
DIVISION
FEB 1 1949