

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Barton County, Sec. 35 Twp. 16 Rge. 11 (EX) (W)

Location as "NE/CNW/SW" or footage from lines SW NE SE

Lease Owner Welch & Olsson Drilling Co. Inc.

Lease Name Nagel Well No. 1

Office Address 203 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 3/1 19 55

Application for plugging filed 3/1 19 55

Application for plugging approved 3/1 19 55

Plugging commenced 3/1 19 55

Plugging completed 3/2 19 55

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner, Box 207, Great Bend, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3430 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	265'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded to 260'. Put in 1/3 sack of hulls. Set plug and cemented with 20 sacks of cement.

Mudded to 35'. Put in 1/3 sack of hulls. Set second plug and cemented with ten sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 11 1955
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Welch & Olsson Drilling Co. Inc.
Address 203 Rule Bldg. Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
R. E. Welch (employee or owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Welch & Olsson Drilling Co. Inc.


(Signature) By [Signature]
203 Rule Bldg. Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 19 55

June 12, 1955

My commission expires

Notary Public.



15009-05548-0000

WELL LOG

WELCH & OLSSON DRILLING COMPANY, INC.
CONTRACTOR: WELCH & OLSSON DRLG. CO. INC.
NAGEL #1
SW NE SE 35-16-11W.
Barton County, Kansas.

ELEVATION: 1935 R.B.
Comm. Drlg: 2/22/55
Compl. Drlg: 3/1/55
Production: D & A.

Casing Record:
265' of 8 5/8" with 150 sacks of cement.

(Figures indicate bottom of Formations.)

<u>FORMATIONS:</u>	<u>DEPTHS:</u>	<u>FORMATION TOPS:</u>
Shale:	540	Anhydrite: (Drlgr.) 750 (+1191)
Red Bed:	750	Heebner: 2985 (-1050)
Anhydrite:	777	Toronto: 3004 (-1069)
Shale & Shells:	1800	Brown Lime: 3084 (-1149)
Shale & Lime:	2425	Lansing-Kans. City: 3097 (-1162)
Lime & Shale:	2515	Conglomerate: 3383 (-1448)
Shale & Shells:	2695	Arbuckle: 3405 (-1470)
Shale & Lime:	2760	
Lime & Shale:	2795	
Lime:	3340	
Lime & Conglomerate:	3390	
Conglomerate:	3415	
Lime:	3430 T.D.	

STATE OF KANSAS,)
) SS:
SEDGWICK COUNTY,)

I hereby certify that the above is a true and correct copy of Drillers Log of well drilled in the SW NE SE of Section 35, Township 16, Range 11 West, Barton County, Kansas.

WELCH & OLSSON DRILLING COMPANY, INC.
BY R. E. Welch
R. E. Welch

Subscribed and sworn to before me this 8th day of March, 1955.

Scott Schubert
Notary Public.

My commission expires:
June 12, 1955

RECORDED
STATE CORPORATION COMMISSION
MAR 11 1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE NO. 35-16-R-11W
BOOK PAGE 10 LINE 41