


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Barton County. Sec. 35 Twp. 16S Rge. 11 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C SW NW SW
Lease Owner The El Dorado Refining Company
Lease Name Frees Well No. "B" #3
Office Address 407 Brown Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-24 19 50
Application for plugging filed 9-25 19 50
Application for plugging approved 9-25 19 50
Plugging commenced 9-25 19 50
Plugging completed 9-25 19 50
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3414 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	3414'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill with heavy mud to 300'. Set plug.
Run 15 sacks cement through drill pipe.
Fill with heavy mud to 30'. Set plug.
Run 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1950

9-30-50

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Sterling Drilling Company
Address Sterling, Ks.

STATE OF Kansas, COUNTY OF Rice, ss.

Rollin Mead (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Rollin Mead
Sterling, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of September, 19 50.

My commission expires 9-17-53

Notary Public.

PLUGGING
FILED SEC. 35 T. 16 S. R. 11 W.
BOOK PAGE 31 LINE 21

15009-05544-0000

STERLING DRILLING CO.

STERLING, KANSAS

WELL LOG ----- FREES "B" #3

Location - C SW/4 NW/4 SW/4 of Section 35-16S-11W, Barton County, Kansas.

Owner - The El Dorado Refining Company
Contractor - Sterling Drilling Company

Commenced - 9-14-50
Completed - 9-24-50

Total Depth - 3414' (w/r)

LOG

CASING RECORD

0- 285	Surface Clay, Sand, Shale, Shells
285- 400	Shale and Shells
400- 745	Shale and Red Bed
745- 775	Anhydrite
775-1050	Shale, Shells
1050-1430	Shale, Shells and Salt
1430-1795	Shale and Lime
1795-2120	Lime
2120-2675	Lime and Shale
2675-3005	Lime
3005-3025	Shale and Lime
3025-3105	Shale
3105-3150	Lime and Shale
3150-3392	Lime
3392-3414	Conglomerate

314' of 8-5/8" Surface Pipe
Cemented with 150 Sacks Cement

PLUGGING
 FILE SEC. 35 T. 46 R. 14 W.
 BOOK PAGE 31 LINE 21

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 30 1950
 CONSERVATION DIVISION
 Wichita, Kansas