

*Complete*


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Stafford County. Sec. 1 Twp. 22 Rge. 14 (E) W (W)  
Location as "NE/CNWxSWx" or footage from lines 1980 FEL and 990 FNL NE/4  
Lease Owner Phillips Petroleum Company  
Lease Name Bordewick Well No. 7  
Office Address Box 287, Gt. Bend, Kan  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed Nov. 1953 19  
Application for plugging filed 2-14-66 19  
Application for plugging approved 2-25-66 19  
Plugging commenced 3-9-66 19  
Plugging completed 3-14-66 19  
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 1-2-66 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. Elving, Box 248, Pratt, Kan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	420	-
				7"	3733	2330'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set. PB 3550' to 3375' with sand; 5 sx cement at 3375'; pulled pipe; Mudded hole to 270'; rock bridge 270 to 260'; dumped 30 sx cement at 260'. Mudded to 30'; rock bridge 30' to 20'; 15 sx cement to surface. Well P&A 2 p.m. 3-14-66. FINAL REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 22 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Knight Casing Pulling Company  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
A. T. Slagle (employee of owner) or (~~owner~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. T. Slagle  
Box 287, Gt. Bend, Kan  
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of March, 1966, 19

My commission expires 10-27-69 Laura Lee Parks Notary Public.

EXPLORATION RECORD

Stafford County, Kansas  
 Sec. 1-22S-14W

Lease Bordewick

Well 7

Formation Name	Top	Base	Remarks
Sand and shells	0	433	
Redbed and shale	433	919	
Redbed, sand and shale	919	1366	
Salt, shale and lime	1366	1755	
Lime and shale	1755	3297	
Lime	3297	3501	
Lime and chert	3501	3554	
Lime	3554	3624	
Lime and shale	3624	3663	
Lime and chert	3663	3714	
Lime	3714	3744	

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 MAR 22 1966  
 CONSERVATION DIVISION  
 Topeka, Kansas