

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-20,016-0001

LEASE NAME Parrish Unit

WELL NUMBER 4 - INP

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 16 TWP. 22 RGE. 13W (C) or (W)

COUNTY Stafford

LEASE OPERATOR Turnco Drilling, Inc.

ADDRESS 3900 Broadway Great Bend, KS 67530

PHONE# (316) 792-2441 OPERATORS LICENSE NO. 30517

Date Well Completed

Character of Well Injection

Plugging Commenced 3-30-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-8-94

The plugging proposal was approved on (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3870'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	281'	none
				5 1/2	3868'	1816'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from foot to foot each set. Sanded bottom to 3390' & dumped 5 sks cement. Shot well @ 2523', worked pipe. Shot @ 2031', left on tension. Worked pipe, shot @ 1816', worked pipe free. Pulled all pipe. Plugged well with 400# hulls, 10 sks gel, 50 sks cement, 10 sks gel, 100# hulls, release plug, 100 sks cement. Shut in @ 250# psi. Max 500#. 60/40 poz 6% gel. Plugging complete.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Turnco Drilling, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso **4-13-94**
STATE CORPORATION COMMISSION
(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 12th day of April, 19 94

Irene Herzberg
Notary Public
IRENE HERZBERG
State of Kansas
My Appl. Exp. Aug. 24, 1997

My Commission Expires:

APR 13 1994
RECEIVED
CONSERVATION DIVISION
Wichita, Kansas