

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 16 Twp. 22 Rge. 13 ~~15~~ (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner Welch & Olsson Drilling Company, Inc.

Lease Name Williams Well No. 1

Office Address 203 Rule Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 2-4 19 54

Application for plugging filed 2-4 19 54

Application for plugging approved 2-4 19 54


Plugging commenced 2-4 19 54

Plugging completed 2-4 19 54

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 148, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3875 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	300'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded to 300'. Cemented and displaced 20 sacks of cement on plug; set second plug at 40'. Cemented and displaced ten sacks of cement on top plug

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Welch & Olsson Drilling Company, Inc.

Address 203 Rule Bldg. Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. E. Welch

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Handwritten Signature]

203 Rule Bldg. Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of February, 19 54

My commission expires June 12, 1955

[Handwritten Signature] Notary Public.

24-7566-S 3-53-20M

PLUGGING
FILED
FEB 16 1954
PAGE 12 LINE 12

RECEIVED
CORPORATION COMMISSION
4-27-54
WICHITA, KANSAS

WELL LOG.

WELCH & OLSSON DRILLING CO., INC.

Elevation: 1905 R.B.

CONTRACTOR: Welch & Olsson Drilling Co., Inc.

Commenced Drlg: 1-24-54

Williams No. 1
SW SW SW Sec. 16-22-13W
Stafford County, Kansas.

Completed Drlg: 2-4-54

Production: D & A

Casing record:

Set 300' of 8 5/8" with 225 sacks cement.

(Figures indicated bottom of formations.)

<u>FORMATIONS:</u>	<u>DEPTHS</u>	<u>FORMATION TOPS.</u>
Surface, Soil & Sand	110'	Heebner 3275 (-1370)
Sand	260'	Toronto 3295 (-1390)
Shale	440'	Brown Lime 3404 (-1499)
Shale & Red Bed	772"	Lansing-Kansas City 3424 (-1519)
Anhydrite	798'	Base Kansas City 3646 (-1741)
Shale & Shells	1650'	Cherty Conglomerate 3699 (-1794)
Shale & Lime	1930'	Viola 3721 (-1816)
Lime with shale stacks	2180'	Simpson 3766 (-1861)
Lime & Shale	2335'	Arbuckle 3825 (-1920)
Shale & Shells	2730'	
Shale & Lime	3303'	
Lime	3305'	
Shale	3404'	
Lime	3702'	
Conglomerate	3721'	
Lime	3766'	
Sand	3825'	
Lime	3875'	T.D.

STATE OF KANSAS,)
) SS:
COUNTY OF SEDGWICK,)

I hereby certify that the above is a true and correct copy of Drillers Log of well drilled in the SW SW SW Section 16, Township 22, Range 13 West, Stafford County, Kansas.

WELCH & OLSSON DRILLING COMPANY, INC.,
BY R. E. Welch
R. E. WELCH

Subscribed and sworn to before me this 8th day of February, 1954.

Seesh Sikes
Notary Public.

My commission expires:
June 12, 1955

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
TOPEKA, KANSAS

PLUGGING
WELL SW SW SW 16-22-13W
CHECK PAGE 12 LINE 12