

ATE OF KANSAS
 ATE CORPORATION COMMISSION
 J. S. Market, Room 2078
 Chita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-02-3-117

API NUMBER 15-185-22,357-0000

LEASE NAME Curtis

WELL NUMBER 2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

 Ft. from S Section Line

 Ft. from E. Section Line

SEC. 16 TWP. 22 RGE. 13W (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 6-11-99

Plugging Completed 6-16-99

EASE OPERATOR Turnco Drilling, Inc.

DRESS Rt. 1 Box 129J Great Bend, Kansas 67530

PHONE# 316, 792-6144 OPERATORS LICENSE NO. 30517

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 3900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	302'	None
				5-1/2"	3898'	1800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug are used, state the character of same and depth placed, from feet to feet each side. Pumped bottom with 50# hulls, 25 sks. cement 1% cc W/50# hulls, displaced plug to 3465'. Shot pipe @2200', 2000' and 1800'. Pulled casing, plugged well with 300# hulls, 10 sks. gel, 50 sks. cement, 10 sks. gel, 100# hulls, released plug and 150 sks. cement, 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524 6-18-99

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Turnco Drilling, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed. That the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 17th day of June, 1999.

[Signature]
 Notary Public

My Commission Expires:

