


15-009-15141-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Location as "NE/CNW&SW" or footage from lines Barton County. Sec. 34 Twp. 16 Rge. 11 (E) (W)
SE NW SW
Lease Owner Hinkée Oil Company
Lease Name Kroutwurst #15 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6/22/70 _____ 19____
Plugging completed 6/26/70 _____ 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3364 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	84	none
				5 1/2"	3364	1798

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3364', ran sand to 3340', ran 5 sacks of cement.
Loaded hole with water, shot pipe at 2000', 1800'; worked pipe
loose and pulled 57 joints. Pumped 3 sacks hulls, 15 sacks mud
and 90 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUL 9 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

Subscribed and sworn to before me this 29th day of June, 19 70

My commission expires 2/15/71

Margaret Melcher
Notary Public.

Casing Record.
 8 5/8 84'
 5 1/2 3364

Kroutwurst No. 15, SE NW SW 34-16-11 Barton Co. Kansas.
 Hinkle Oil Company
 Contractor J. B. Hinkle.
 Commenced 8-21-51 Completed 8-31-51
 Elevation 1934

0	25	surface clay
25	55	rock
55	74	shale
74	80	sand
80	84	shale
84	170	shale and sand
170	479	sand and shale
479	743	shale and shells
743	775	anhydrite
775	785	red bed and shale
895	1160	shale and shells
1160	1620	shale and shells
1620	1684	shale and broken lime
1684	2785	lime and shale
2785	2902	lime
2902	3177	lime and shale
3177	3364	lime
3364	3365	Arbuckle Lime
T.D.	3365	

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 28 1970
 CONSERVATION DIVISION
 Wichita, Kansas

Tops		
Brown Lime	3082	(-1148)
Lansing	3101	(-1167)
Arbuckle	3364	(-1431)

State of Kansas)
) ss
 County of Sedgwick)

I hereby certify that the above is a true and correct log as compiled from the daily drilling reports kept on said well.

And further affiant saith not.

J. B. Hinkle

Subscribed to and sworn to before me this 21st day of September, 1951.

M. A. Upton
 N.P.

My commission expires 1-17-54