

WELL PLUGGING RECORD


15-09-15 1380000

KC 4-3-17

JUN 21 1958

Barton County. Sec. 34 Twp. 16 Rge. 11 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW



Locate well correctly on above
Section Plat

Lease Owner Hinkle Oil Co.
Lease Name Kroutwurst #12 Well No. _____
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6-16-58 _____ 19____
Plugging completed 6-18-58 _____ 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3371 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	95'	none
				5-1/2"	3362'	1209'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked in hole, found pipe loose at 1202'; pulled 10 jts., mud filled to 1140'. Filled w/sand to 1100' and ran 5 sacks of cement with dump bailer. Pulled rest of casing. Bailed to 260', set a 10' rock bridge and ran 35 sacks of cement. Mudded the hole to 20', set rock bridge and ran 5 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) J. B. Hinkle

(Address)

Subscribed and Sworn to before me this 19th day of June, 19 58

My commission expires 9-27-58

Notary Public.



15-009-15138-0000

Casing Record.
95' 8 5/8"
3362' 5 1/2"

Krautwurst No. 12. NE NE SW 34-16-11 Barton County, Kans.
Hinkle Oil Company
Contractor: J. B. Hinkle
Commenced 7-11-51 Completed 7-21-51
Elevation 1935

0	20	Surface soil and rock
20	40	Rock and shale
40	60	Shale and shells
60	75	Sand
75	95	Shale and shells
95	170	Shale and clay
170	220	Sand and shale
220	263	Red bed and shale
263	720	Shale and shells
720	725	Shale
725	760	Anhydrite
760	950	Shale-pyrite streaks
950	1110	Shale-shells and streaks pyrite
1110	1200	Salt-shale and shells
1200	1235	Shale-shells and streaks of pyrite
1235	1515	Shale and shells
1515	1635	Broken lime and shale
1635	2250	Lime and shale
2250	2440	Shale and shells
2440	2600	Shale
2600	2945	Lime and shale
2945	3317	Lime
3317	3361	Lime and shale
3361	3364	Arbuckle
T. D.		

Tops:

Top Brown Lime	3076 (-1150)
Top Lansing-Kansas	
City	3092 (-1166)
Arbuckle	3361 (-1438)

State of Kansas,)
County of Sedgwick,) ss

I hereby certify that the above is a true and correct log as compiled from the daily drilling reports kept on said well.
And further affiant saith not.

REC
STATE CORP.

JUN 21 1951
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
IT SEC 34 T 16 R 11W
BOOK PAGE 109 LINE 35

J. B. Hinkle

Subscribed to and sworn to before me this 2nd day of August, 1951.

Murphy A. Lupton
N. P.

My commission expires 1-17-51