


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Barton County. Sec. 34 Twp. 16 Rge. 11 (E) (W)
Location as "NE/CNWxSWx" or footage from lines SW SE SW
Lease Owner Hinkle Oil Company
Lease Name Kroutwurst Well No. 8
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 2/27/67 _____ 19____
Plugging completed 3/ 2/67 _____ 19____
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3337 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	102	none
				7"	3336	1715.48

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Raised mast, checked hole to 3330', sanded back to 3300' and ran 5 sacks of cement. Cleaned cellar, rigged up on 7" casing. Worked pipe to 12" tension. Shot pipe at 2083', no change in tension. Worked pipe, no change in tension. Spotted oil, pumped 35 barrels of oil and chased plug to 2030'. Worked pipe to 18" tension, checked hole and shot pipe at 1990', 1933', 21" tension. Shot pipe at 1869', 1778', and 1713'. Worked pipe loose and pulled 20 joints of 7" pipe. Finished pulling 7" casing, cleared floor, loaded rack, had welder out to weld connection on surface. Pumped 20 sacks of mud and 100 sacks of cement. Lowered mast, racked unit and tallied pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

APR 21 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of March, 1970

My commission expires October 22, 1970

[Signature]
Notary Public.

15-00915134-0000

Kroutwurst No. 8. SW SE SW 34-16-11 Barton County, Kansas.
Hinkle Oil Company
Contractor: J. B. Hinkle.
Commenced 8-23-50 Completed 9-2-50
Elevation 1898

Casing Record.
100' 11 1/2"
3336' 5"

0	100	surface
100	185	shale
185	250	red bed and sand
250	345	shale and red bed
345	505	shale and sand
505	718	red bed and shale
718	745	Anhydrite
745	1045	shale shells and red bed
1045	1445	shale, salt and shells
1445	1670	shale, shells and lime
1670	1840	lime and shale
1840	1970	lime
1970	2140	lime and shale
2140	2325	shale and shells
2325	2780	lime and shale
2780	2940	lime
2940	2990	lime and shale
2990	3060	lime
3060	3135	lime and shale
3135	3205	lime
3205	3330	lime and shale
3330	3336	lime T.D.

RECEIVED
STATE COMMISSION
JAN 30 1957
REGISTRATION DIVISION
Topeka, Kansas

Tops:

Heebner shale	2949	(-1049)
Brown Lime	3052	(-1152)
Lansing	3074	(-1174)
Arbuckle	3333	(-1433)

State of Kansas,)
) ss
County of Sedgwick,)

I hereby certify that the above is a true and correct log as compiled from the daily drilling reports kept on said well.
And further affiant saith not.

J. B. Hinkle

Subscribed to and sworn to before me this 20th day of September, 1950.

Murphy A. Upton
N.P.

My commission expires 1-17-54