

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 18 1966

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasOperator's Full Name Petroleum, Inc., c/o Pipe Pullers, Inc.Complete Address: Box 486, Ellinwood, KansasLease Name Strobel (Smallwood Lan-KC Unit#2-1) Well No. # 1Location SW SW NW Sec. 2 Twp. 22 Rge. 14 (E) (W) WCounty Stafford Total Depth 3835'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Pipe Pullers, Inc.Address: Box 486, Ellinwood, Kansas License No. 462Operation Completed: Hour 10:30AM Day 14th Month March Year 1966

The Above well was plugged as follows:

325' of 8 5/8" surface pipe, cemented with 225 sacks. 3680' of 5 1/2" long string, cemented with 100 sacks. Plug back T.D. 3662'. Top perforation 3561'. Bottom of the hole was sanded to 3425', and cemented with 5 sacks, through the dump bailer. 3004' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 310', rock bridge from 310' to 300', 8 sacks of cement was mixed in a barrel, and put on plug at 300', through the dump bailer, and let set over-night. Next morning hole was bailed dry, and 17 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 3/18/66INV. NO. 2890-W