

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1966
CONSERVATION DIVISION
Wichita, Kansas
10-31-66

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Phillips Petroleum Company

Complete Address: Box 287, Great Bend, Kansas

Lease Name Bordewick Well No. # 8

Location App. C NE SE NE Sec. 1 Twp. 22 Rge. 14 (E) (W) W

County Stafford Total Depth 3640'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 9:45AM Day 28th Month Oct. Year 1966

The Above well was plugged as follows:

394' of 8 5/8" surface pipe, cement circulated. 3634' of 5 1/2" long string,
cemented with 150 sacks. Plug abck T.D. 3538'. Top perferation 3406'. Bottom
of the hole was rocked to 3295', and cemented with 5 sacks, and 7' of sand,
and 2 sacks of cement, cemented through the dump bailer. 2615' of 5 1/2" long
string was recovered from the hole. Bridge plug was pushed in fluid to 300',
rock bridge from 300' to 290'. 5 sacks of cement was mixed in a barrel, and
put on plug at 290', through the dump bailer, and let set over-night. Next day
hole was bailed dry, and 20 sacks of cement was added to the plug. Hole was
filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks
to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/31/66

INV. NO. 4209-W

Signed: Archie Elving
Well Plugging Supervisor