

KANSAS

R STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name E.L. Browning

Complete Address 2007 Polk Great Bend, Ks

Lease Name Wright Well No. 1

Location NW/SE/SW Sec. 1 Twp. 22 Rge. 14 (E) (W) W

County Stafford Total Depth 3755

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 10: AM Day 8 Month 1 Year 1971

The above well was plugged as follows:

345 ft of 8 5/8 surface pipe circulated. 3755 ft of 4 1/2 long string
cemented with 100 sacks. No casing pulled. Production string cemented
in. Sand back to 3300 ft, 4 sacks cement with bailer. Set 20 ft.
rock bridge at 480 to 500 ft. Fill 4 1/2 with 40 sacks cement. to
surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-12-71

INV. NO. 3195-W

Signed: *L. Russell Biberstein*
Well Plugging Supervisor

E. L. Browning

Wright # 1

NW SE SW Sec. 1 - 22 - 14W

Stafford County, Kansas

15.185-19427-0000

Hebner
Brown Lime
Kansas City
Viola
Simpson
Arbuckle

TOP FORMATIONS

3273'

3376'

3408'

3655'

3692'

3743'

RECEIVED
STATE CORPORATION COMMISSION
OFC 28 1970
CONSERVATION DIVISION
Wichita, Kansas