

90
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
KANSAS STATE CORPORATION COMMISSION
MAR 18 1966
3-18-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Phillips Petroleum

Complete Address: Box 287, Great Bend, Kansas

Lease Name Bordewick Well No. # 7

Location C S/2 NW NE Sec. 1 Twp. 22 Rge. 14 (E) (W) W

County Stafford Total Depth 3733'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 2:30 PM Day 14th Month March Year 1966

The Above well was plugged as follows:

420' of 10 3/4" surface pipe, cemented with 400 sacks. 3733' of 7" long
string, cemented with 200 sacks. Plug back T.D. 3550'. Top perferation 3400'.
Bottom of the hole was sanded to 3375', and cemented with 5 sacks, through
the dump bailer. 2315' of 7" long string was recovered from the hole. Bridge
plug was pushed in fluid to 277', rock bridge from 277 to 270'. 5 sacks of
cement was mixed in a barrel, and put on plug at 270', through the dump bail-
er, and let set over week end. Hole was bailed dry, and 25 sacks of cement
was added to the plug. Hole was filled with mud to 40', rock bridge from 40'
to 30', and cemented with 15 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlene Elving
Well Plugging Supervisor

DATE 3/18/66
INV. NO. 2893-W