

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION
JUL 18 1966
7-13-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name L. K. Parrish

Complete Address: 714 Fourth National Bank Bldg., Wichita, Kansas

Lease Name John F. Williams Well No. # 1

Location SW SW SW Sec. 16 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3875'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down

Plugging Contractor: Sage Drilling Company, Inc.

Address: 500 Bitting Bldg., Wichita, Kansas License No.

Operation Completed: Hour 1:15PM Day 9th Month July Year 1966

The Above well was plugged as follows:

300' of 8 5/8" surface pipe, cement circulated. Fluid level in the hole
was at 120', 1st cementing plug and 1/4 sack of hulls was pushed in fluid
to 260', and cemented with 25 sacks, through the drill pipe. Hole was
filled with drilling mud to 40', 2nd cementing plug, bridged with 1/2
sack of hulls on fluid at 40', and cemented with 10 sacks to the base
of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving

Well Plugging Supervisor

DATE 7/13/66INV. NO. 3563-4