

KANSAS
STATE CORPORATION COMMISSIONCONSERVATION DIVISION AGENT'S REPORT
RECEIVED
STATE CORPORATION COMMISSIONJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

APR 5 1965

4-5-65

CONSERVATION DIVISION
Wichita, KansasOperator's Full Name E. K. EdmistonComplete Address: 501 First National Bank Bldg., Wichita, KansasLease Name Cassady Well No. # 1-ALocation NE NE NW Sec. 16 Twp. 22 Rge. 13 (E) (W) WCounty Stafford Total Depth 3844'Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: This hole was a wash downPlugging Contractor: E. K. Edmiston Drilling Company Inc.Address: 501 First National Bank Bldg., Wichita, Kansas License No. Operation Completed: Hour 9:45PM Day 31st Month March Year 1965

The Above well was plugged as follows:

300' of 8 5/8" surface pipe, cemented with 250 sacks. Fluid level in
the hole was at 140'. 1st cementing plug and 1/2 sack of hulls was pushed
in fluid to 275', and cemented with 25 sacks, through the drill pipe.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with hulls on fluid at 40', and cemented with 10 sacks to the
base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICEDSigned: Archie Elving
Well Plugging SupervisorDATE 4/5/65INV. NO. 929-W