

KANSAS

Al

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 21 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name E.K. Edmiston
 Complete Address 801 1st Natl Bldg. Wichita, Ks
 Lease Name Curtis Well No. 2
 Location NW/SE/SE Sec. 16 Twp. 22 Rge. 13 (E) (W) W
 County Stafford Total Depth 3838
 Abandoned Oil Well X Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated
 Plugging Contractor Russ Casing Pulling Co. Inc.
 Address Box 1082 Great Bend, Ks License No. 623
 Operation Completed: Hour 4:30 PM Day 19 Month 1 Year 1971

The above well was plugged as follows:

265 ft of 8 5/8 surface pipe cemented with 225 sacks. 3826 ft of 4 1/2
long string cemented with 125 sacks. Top perf. 3582 ft. Sand back
to 3560 ft, 4 sacks cement with bailer. Pulled 2917 ft of 4 1/2.
Pumped 2 sacks hulls, 15 sacks gel. & 100 sacks cement to base of
cellar. Sun Cementing Co. Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

Signed: *W. Russell Bihirstin*
Well/Plugging Supervisor

1/21/71
3245-U