

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Parrish Oil Co.
Complete Address 714 4th Natl Bldg. Wichita, Ks
Lease Name Mary Parrish Well No. 3
Location NW/NW/SE Sec. 16 Twp. 22 Rge. 13 (E) W (W) W
County Stafford Total Depth 3840
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Santa Fe Pipe & Supply, Inc.
Address Box 562 Great Bend, Ks License No. 574
Operation Completed: Hour 1:00 PM Day 11 Month 2 Year 1971

The above well was plugged as follows:

289 ft of 8 5/8 surface pipe cemented with 250 sacks. 3824 ft of
5 1/2 long string cemented with 150 sacks. Top perf. 3575 ft. Set
plug at 3500 ft, sand to 3450 ft, 5 sacks cement with bailer. Pulled
2918 ft of 5 1/2. Pump 3 sacks hulls, & 15 sacks gel. & 100 sacks
cement to surface.

Halliburton Services Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/17/71

INV. NO. 3350-W

Signed: D. Russell Biberstein
Well Plugging Supervisor