


15-009-19294-0000

Form CP-3
Rev. 6-26-62

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAR 19 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin Drilling Company

Complete Address: 617 Union Center, Wichita, Kansas

Lease Name Freee Well No. # 3

Location NE SE NW Sec. 34 Twp. 16 Rge. 11W (E) (W)

County Barton Total Depth 3384

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Co.

Address: Box 304, Great Bend, Kansas License No. # 2

Operation Completed: Hour 12 Noon Day 15 Month 3 Year 1963

The Above well was plugged as follows:

8 5/8" 301' Gwc.

Sanded hole back to 3365' & dumped 4 sax cement with dump bailer.

Pulled pipe. Mudded hole to 300'; set rock bridge; dumped 8 sax cement

on bridge. Let set over-nite, bailed hole dry & displaced 17 sax cement.

Mud to 40'; set rock bridge; displaced 10 sax cement, cementing to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don Truman
Well Plugging Supervisor

DATE 3/19/63

INV. NO. 6746-w