

15-009-15137-0000

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1962

CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Barton

Location: NW NW SE Sec. 34 Twp. 16 Rge. 11W (E) _____ (W) _____

Name of Field: _____ Total Depth: 3390

I have this date completed supervision of plugging of:

Lease Name: Krautwurst Well No. 11

Operator's Full Name: Hinkle Oil Co.

Complete Address: 1016 Union Center, Wichita, Kansas

Plugging Contractor Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 2:00 PM Day 15 Month 6 Year 1962

The above well was plugged as follows:

8 5/8" 102' Cwc.

Sanded hole back to 3370' & dumped 5 sax cement with dump bailer.

Pulled pipe to 300'; displaced 10 sax mud & 25 sax cement thru pipe.

Pulled pipe to 100' & displaced 20 sax cement thru pipe with Halliburton

Cementing Company's pump truck. Pulled remaining pipe; set rock bridge

@ 40' & displaced 10 sax cement, cementing to base of cellar.

Signed: Don Truman
Conservation Division Agent

Reviewed: Harold Morris
Field Supervisor

Remarks:

INVOICED

DATE 6/22/62

INV. NO. 5239-W