

15-009-15133-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*X* STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 10 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Hinkle Oil Company

Complete Address 1016 Union Center Wichita, Kansas 67202

Lease Name Kroutwurst Well No. 7

Location NW NW SW Sec. 34 Twp. 16 Rge. (E) (W)11

County Barton Total Depth 3370

Abandoned Oil Well XXX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 3 P Day 7 Month 8 Year 1970

The above well was plugged as follows:

Total Depth 3370' 8 5/8 csg set at 101' cwc 75 sk.

5 1/2 csg set at 3369' cw 100. sk cmt. Dakato squeezed to surface with 500 sk cmt.

Filled 5 1/2 csg W/sd (3360-3370) Dumped 5 sk cmt W/dump bailer. (3320-3360)

Filled 5 1/2 W/mud to 400' -- set rock & sand bridge (385-400)

Filled to surface with 2 1/2 yds readymix cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/10/70

INV. NO. 2358-W

Signed: [Signature]  
Well Plugging Supervisor