

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SE-SE-SE

SEC. 34 TWP. 16 RGE. 11-w

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 6 Lease Kroutwurst **KROUTWURST**

Operator Wichita Oil Co Address 7916 N. 10th St. Bldg. Wichita-Kans

Field \_\_\_\_\_ County Barton

Total Depth 3398 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 1/2 - 264 ft. Circulated with cement.  
5 1/2" casing set at 3393 ft. 50 sacks of cement. Plugged  
back to 3380 ft with rock & sand. Mixed 5 sacks  
of cement at 3380 ft. Shot off & hulled the 5 1/2" casing.  
I used to 300 ft. Set rock bridges & 25 sacks of  
cement at 300 ft. Used to 65 ft. Plug &  
10 sacks of cement at the surface.*

**RECEIVED** 3-7-53  
STATE CORPORATION COMMISSION  
MAR - 7 1953. W. Stouck  
District Conservation Agent  
CONSERVATION DIVISION  
Wichita Kansas - 3 - 53

**PLUGGING**  
FILE SEC 34 TWP 16 R 11-w  
BOOK PAGE 23 LINE 6