


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Stafford County, Sec. 9 Twp. 22 Rge. 12 (E) (W)

Location as "NE/CNW<sup>1</sup>/<sub>4</sub>SW<sup>1</sup>/<sub>4</sub>" or footage from lines SW SW SW  
Lease Owner Murfin Drilling Co., et al  
Lease Name Teichman Well No. 1  
Office Address 910 Un. Natl. Bank Bldg., Wichita, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 9-26-51 19  
Application for plugging filed 9-26-51 19  
Application for plugging approved 9-26-51 19  
Plugging commenced 9-26-51 19  
Plugging completed 9-26-51 19  
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
Producing formation Depth to top Bottom Total Depth of Well 3700 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	275	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded to 270'. Set plug and displaced 15 sacks cement. Mudded to 35'. Plug set & displaced 10 sacks cement to surface.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Ash-Mur Drilling Co.  
Address Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
W. R. Murfin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W.R. Murfin  
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 22nd day of October, 19 51

My commission expires 6-4-55

Kelen Horise  
RECEIVED  
CORPORATION COMMISSION  
Notary Public.

PLUGGING  
FILE SEC 9 T 24 R 12 W  
BOOK PAGE 112 LINE 32

OCT 23 1951  
CONSERVATION DIVISION  
Wichita, Kansas


KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Murfin Drilling Co., et al  
FARM Teichman NO. 1

SEC. 9 T. 22 R. 12W  
LOC. SW SW SW

TOTAL DEPTH 3700  
COMM. 9-12-51 COMP. 9-26-51  
SHOT OR TREATED  
CONTRACTOR Ash-Mur Drilling Co.  
ISSUED

COUNTY Stafford  
KANSAS



CASING

20	10
15	8 272
12	6
13	5

ELEVATION 1868 D.F.

PRODUCTION Dry

FIGURES INDICATE BOTTOM OF FORMATIONS

156 clay & sand  
252 sand & shells  
272 shells & red bed  
800 red bed  
950 shale & shells  
980 Anhydrite  
1480 shale-shells  
1625 lime  
1795 lime sandy  
1955 lime-shale  
2067 lime  
2545 shale-lime  
2540 shale-shells  
2630 lime  
2765 lime-shale  
3169 lime  
3321 shale  
3652 lime  
3700 shale-sand

Tops	
Heebner	3170 (-1299)
Brown Lime	3302 (-1431)
Lans.-K.C.	3322 (-1451)
Cherty. Congl.	3574 (-1703)
Viola	3586 (-1715)
Simpson	3636 (-1765)
Arbuckle	3691 (-1820)

STATE OF KANSAS )  
                          ) SS:  
SEDGWICK COUNTY)

I, W. R. Murfin, of the Murfin Drilling Co., upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Teihhman well.

W. R. Murfin  
W. R. Murfin

Subscribed and sworn to before me this 22nd day of October, 1951.

Helen Strine  
Notary Public

My Commission Expires: 6-4-55

**PLUGGING**  
FILE SEC 9 T 22 R 12W  
BOOK PAGE 11 LINE 32

**RECEIVED**  
STATE CORPORATION COMMISSION  
OCT 23 1951  
CONSERVATION DIVISION  
WICHITA, KANSAS