


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 9 Twp. 22S Rge. (E) 12 (W)
Location as "NE/CNW/SW" or footage from lines SW-NE-SW
Lease Owner Aspen Drilling Co.
Lease Name Brening Well No. 1
Office Address P. O. Box 783, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 26 19 69
Application for plugging filed Nov. 4 19 69
Application for plugging approved 19
Plugging commenced October 26 19 69
Plugging completed same 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ralph J. Warren
Producing formation Depth to top Bottom Total Depth of Well 3690 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 450', 50 sacks cement;
mud to 280', 25 sacks cement
mud to 40', wood plug and 10 sacks cement;
2 sacks cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION
NOV 5 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Aspen Drilling Co.
Address P. O. Box 783, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
William S. Schachle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William S. Schachle
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of November, 19 69

My commission expires April 18, 1972

Theora Holleman
Theora Holleman Notary Public.

DRILLERS LOG

COMPANY: Aspen Drilling Co.
 CONTRACTOR: Aspen Drilling Co.
 LEASE NAME: Brensing #1
 LOCATION: SW-NE-SW Sec. 9-T22S-R12W
 Stafford County, Kansas
 ELEVATION: 1872 K.B.
 SURFACE CASING: 7 jts. (282') 8 5/8"
 COMMENCED: October 17, 1969
 COMPLETED: October 26, 1969
 ROTARY TOTAL DEPTH: 3690'

<u>FORMATION</u>	<u>DEPTH</u>	
Sand & Shale	735	Ran 7 jts. (282') 8 5/8" casing set at 289' with 250 sacks cement. Cement circulated.
Anhydrite	915	
Shale	1170	
Shale & Lime	1815	
Lime & Shale	1870	DST #1 3374-3406'
Shale & Lime	1998	DST #2 3502-3525'
Lime & Shale	2235	DST #3 3685-3690'
Shale & Lime	3166	
Lime & Shale	3490	D & A
Shale & Lime	3525	
Lime	3557	
Lime & Chert	3626	
Shale	3630	
Shale & Lime	3646	
Lime	3690	
RTD	3690	

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 5 1969
 CONSERVATION DIVISION
 Wichita, Kansas

AFFIDAVIT

State of Kansas)
) ss:
 County of Barton)

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

William S. Schachle
 William S. Schachle AFFIANT

Subscribed and sworn to before me this 4th day of November, 1969

Theora Holleman
 Theora Holleman, Notary Public