

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH

Section flat grid for well location

Locate well correctly on above
Section Flat

Stafford County. Sec. 9 Twp. 22 Rge. (E) 12 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. C. W. 1/2 SW 1/4 NW 1/4
Lease Owner. Barnett Oil Company
Lease Name. Teichmann Well No. 1
Office Address. 417 First National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed. March 5 1949
Application for plugging filed. March 5 1949
Application for plugging approved. March 5 1949
Plugging commenced. March 5 1949
Plugging completed. March 5 1949
Reason for abandonment of well or producing formation. Dry Hole

If a producing well is abandoned, date of last production. - 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well. C. D. Stough
Producing formation. Depth to top, Bottom Total Depth of Well 3705 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Surface Pipe, 8 5/8", 278, None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3705' to 278'. Set plug at 278' and filled surface pipe with cement to 231'. Filled surface pipe with heavy mud from 231' to 30'. Set plug at 30' and filled casing with cement to bottom of cellar.

RECORDED

MAR 24 1949 3-24-49

STATE CORPORATION COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Barnett Oil Company
Address 417 First National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Hunter (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. R. Hunter

First National Bank Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 22nd day of March 1949.

Adelaide Olivier Notary Public.

My commission expires May 12, 1951

PLUGGING
FILE SEC 9 T 22 R 12 W
BOOK 86 PAGE 1

BARNETT OIL COMPANYLOG OF TEICHMANN WELL NO. 1C 1/2 SW 1/4 NW 1/4 SECTION 9-22S-12W, STAFFORD COUNTY, KANSAS

Formation	From	To	Remarks
Surface Clay	0	45	
Sand	45	72	
Sand and Clay	72	195	
Sandy Clay	195	225	
Red Bed	225	800	Set 8 5/8" Surface pipe at 278 feet; cemented with 300 sacks of cement.
Red Bed and Shells	800	1095	
Shale and Shells	1095	1545	
Broken Lime and Shale	1545	1730	
Lime and Shale	1730	1925	
Broken Lime	1925	2000	
Lime and Shale	2000	2010	
Lime	2010	2195	
Lime and Shale	2195	2270	
Shale and Shells	2270	2625	
Lime and Shale	2625	2670	
Shale and Shells	2670	2750	
Lime and Shale	2750	2925	
Hard Lime and Chert	2925	2975	
Lime	2975	3184	
Shale and Lime	3184	3310	
Shale	3310	3332	
Lime	3332	3472	
Lime and Shale	3472	3505	
Lime	3505	3630	
Lime and Shale	3630	3695	
Cherty Lime	3695	3705	
Total Depth		3705	Dry and abandoned.

RECORDED

C. O. BARNETT

MAR 24 1949

STAFFORD COUNTY REGISTRATION
COMMISSION
KANSAS

PLUGGING
FILE SEC 9 T 22 R 12 W
PAGE 86 LINE 1