

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15.185-01975-0000

LEASE NAME Siefkes "C"

WELL NUMBER #7

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 3 TWP. 22S RGE. 12 (E) or (W)

COUNTY Stafford

Date Well Completed 3-9-40

Plugging Commenced 3-1-91

Plugging Completed 3-1-91

RECEIVED  
STATE CORPORATION COMMISSION

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

MAY 13 1991 3-13-91

CONSERVATION DIVISION

Wichita, Kansas

LEASE OPERATOR Hallwood Petroleum, Inc.

ADDRESS P.O. Box 378111, Denver, CO 80237

PHONE# (303) 850-6337 OPERATORS LICENSE NO. 3613

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-1-91 (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3601 Bottom 3607 T.D. 3607

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	Surf	246	8 5/8"	246'	0
		Surf	3601	5 1/2"	3601'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from          feet to          feet each set 250# hulls, 25 sx 60/40 poz, 6% gel w/50# CSH mixed within 20 sx gel. 5 1/2" wiper plug disp. to 700' w/17 BW. Shot csg @679', Pmpd 210 sx 60/40 poz, 6% gel cmt circ. Had cmt returns to surf between 5 1/2" & 8 5/8" annulus. Closed annulus space in & squeezed 15 sx 60/40 poz, 6% gel into 5 1/2" csg.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address P.O. Box 579, Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: \_\_\_\_\_

STATE OF Colorado COUNTY OF Denver, ss.

Suzanne E. Meadows

(Employee of Operator) or (Operator) c

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Suzanne E. Meadows

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 10th day of May, 1991

Judy E. Atkins  
Notary Public

My Commission Expires: 4/19/93