

1 060615

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,204-0000

NW NE, SEC. 6, T 22 S, R 20 (W/K)

4620 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5141

Lease Name Smith Well # 1

Operator: Zenith Drilling Corporation
Name & Address: 505 Fourth Financial Center

County Pawnee (MISSISSIPPI) 145.02

Wichita, KS 67202

Well Total Depth 4462 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 376

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Sterling Drilling Company License Number 5142

Address Box 129, Sterling, KS 67579

Company to plug at: Hour: 2:00 pm Day: 16 Month: July Year: 19 85

Plugging proposal received from Jim Shriner

(company name) Sterling (phone) 316-278-2131

Elevation 2258'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1360'

1st plug at 1360' with 50 sx cement

2nd plug at 840' with 70 sx cement

3rd plug at 420' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:40 pm Day: 16 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1360' with 50 sx cement, 2nd plug at 840' with 70 sx cement, 3rd plug at 420' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1985 7-22-85

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(if additional description is necessary, use BACK of CURRIS Form 1001
Wichita, Kansas

INVOICED

DATE 7-24-85

INV. NO. 9108

Signed Paul A. Luther (TECHNICIAN)