

To: 1 070770
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-12
API NUMBER 15-083-20,848-0000
SE SE NW, SEC. 32, T 22 S, R 21 W/E
2970 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9732

Lease Name Bauer-Reece Well # 1

Operator: Apollo Energies
Name & Address 520 Ridgeway
Pratt, KS 67124

County Hodgeman 148.20
Well Total Depth 4560 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 343

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 12 Month: 12 Year: 19 89

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4560' PBTD 4536' Perfs at 4492-4502' Elevation 2226' GL

1st plug sand back to 4445' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 20 sx gel and 50 sx cement at 1400',

3rd plug pump 70 sx cement at 700, 4th plug pump 40 sx cement at 370',

5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:45 p.m. Day: 12 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4445' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 20 sx gel and 50 sx cement at 1400',

3rd plug pumped 70 sx cement at 700',

4th plug pumped 40 sx cement at 370',

5th plug pumped 10 sx cement at 40'. Good circulation throughout.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-3-1990

INV. NO. 26853

Signed Dan Hoover
(TECHNICIAN)

STATE CORPORATION COMMISSION
RECEIVED
10-19-89
WICHITA, KANSAS
CONSERVATION DIVISION
WICHITA, KANSAS
NOV 10 1989